



- NOTES
1. NORMALLY OPEN, CLOSURES TO ALARM
 2. NORMALLY CLOSED, OPENS TO ALARM
 3. FOR PILOT DUTY ONLY, 250VAC, 30VDC, 10A. MAX. LOAD
 4. ALL CONTACTS SHOWN DE-ENERGIZED
 5. TERMINALS H AND N RATED 100VA, 120VAC MAX. LOAD
 6. REFER TO TRANSFORMER NAMEPLATE FOR CONNECTION INFORMATION
 7. TO PUMP RUNNING REMOTE ALARM CIRCUITS
 8. TO PHASE REVERSAL REMOTE ALARM CIRCUITS
 9. TO PHASE REVERSAL REMOTE ALARM CIRCUITS
 10. SPARE TERMINAL PROVIDED FOR PARALLEL CONNECTION
 11. OF REMOTE ALARMS (IF REQUIRED)

ADDED TITLE BLOCK		E	280820	JMW	TEF	09-12-19
ADDED TEST SOLENOID & AUDIBLE ALARM TO COMPLY WITH NEW FM STD		D	228528	JC	TEF	11-15-09
REVISION DESCRIPTION		REV	ECN NO	BY	APP	DATE
WIRING SCHEMATIC		FTA1300		DRAWING NUMBER		
OPEN TRANSITION WYE-DELTA FIRE PUMP CONTROLLER		FTA1300		WS1300-50		
DWG REV		E	ECN NO 280820	SHEET 1 OF 1		

SIZE B BY DATE
 DRAWN BY TEF 05-10-02
 FINAL APPROVAL TEF 05-10-02

© Firetrol, Inc. Not for construction.
 Subject to change without notice.

All rights reserved. The drawing and the information contained or depicted herein are the sole property of Firetrol, Inc. Copies are communicated to the recipient in strict confidence and may not be retransmitted, published, reproduced, copied or used in any manner, including as the basis for the manufacture or sale of any products, without the express prior written consent of Firetrol, Inc.